



15-167-21732-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

June 18, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Charley McDonald of Isern-Shultz Oil & Gas has this date requested permission to plug the following described well:

Operator's Full Name: Isern-Schultz Oil & Gas, Inc.

Complete Address: Box 486, Ellinwood, Kansas 67526

Lease Name: Brungardt Well No. 1

Location: SE NE SW Sec. 15 Twp. 13 Rge. 15 ~~XXX~~ (E) (W)

County: Russell Total Depth: 3330'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. McDonald was instructed to plug the well as follows:

8-5/8"-198' set at 222'-135 sacks. Circulate and fill hole with mud.

Pump 50 sacks cement through drill pipe at 620'. Pump 30 sacks cement

through drill pipe at 225'. Fill hole with mud to 40'. Push plug and 1/2

sack hulls to 40' and cap hole with 10 sacks cement. Cement rathole with

10 sacks cement.

Elev. 1866 GL Anhydrite 936-69'

RECEIVED  
STATE CORPORATION COMMISSION  
06-23-1981  
JUN 23 1981

Very truly yours,

Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas