

State of Kansas



FORM CP-2

15-167-21798-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: John O. Farmer, Inc.

Complete Address: 307 W. Wichita Ave., Russell, Ks. 67665

Lease Name: Brungardt Well No. #2

Location: NW/SE/SE Sec. 15 Twp. 13S Rge. 15 (E) (W)

County: Russell Total Depth: 3310'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8"-229' S.P. cuc. w/150 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @ 720' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.

5 sacks of cement in rat hole, and 5 sacks of cement in mousehole.

Very truly yours,

RECEIVED  
STATE CORPORATION COMMISSION

[Signature]  
Conservation Division Agent

OCT 26 1981  
10-26-1981  
CONSERVATION DIVISION  
Wichita, Kansas