

State of Kansas



15-1167-02077-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1974
10-21-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. A. F. Schmidt of A. F. Schmidt has this date requested permission to plug the following described well:

Mr. A. F. Schmidt guarantees payment of the plugging fee.

Operator's full Name: A. F. Schmidt

Complete Address: P. O. Box 662, Russell, Kansas 67665

Lease Name: McKune Well No. # 4

Location: SE NE SW Sec. 17 Twp. 13 Rge. 15 (E)(W) W

County: Russell Total Depth 3306 Oil Well XX

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" csg. 595' Cwc. Perf. 3012'

Sanded hole back to 2975' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, released

plug, & displaced 100 sax cement with Allied Cementing Company's pump

truck, cementing from 330' to base of cellar.

Very truly yours,

John Unruh
Conservation Division Agent