

State of Kansas



15-167-03887-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1974  
10-21-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. A. F. Schmidt of A. F. Schmidt has this date requested permission to plug the following described well:

Mr. A. F. Schmidt guarantees payment of the plugging fee.

Operator's full Name: A. F. Schmidt

Complete Address: Box 662, Russell, Kansas 67665

Lease Name: McKune Well No. # 2

Location: SE SE SW Sec. 17 Twp. 13 Rge. 15 (E)(W) W

County: Russell Total Depth 3378 Oil Well

Gas Well  Input Well  SWD Well XX D & A  Lost Hole

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" csg. 486' Cwc. Perf. 3040'

Sanded hole back to 3000' & dumped 4 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, released

plug, & displaced 100 sax cement with Allied Cementing Company's pump

truck, cementing from 330' to base of cellar.

Very truly yours,

Law Leman  
Conservation Division Agent