

State of Kansas



15-167-00565-00-00

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 21 1974  
10-21-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. A. F. Schmidt of A. F. Schmidt has this  
date requested permission to plug the following described well:

Mr. A. F. Schmidt guarantees payment of the plugging fee.

Operator's full Name: A. F. Schmidt

Complete Address: P. O. Box 662, Russell, Kansas 67665

Lease Name: McKune Well No. # 1

Location: NE SE SW Sec. 17 Twp. 13 Rge. 15 (E)(W) W

County: Russell Total Depth 3275' Oil Well XX

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Albert Unruh was instructed to plug the well as follows:

8 5/8" csg. 318' Cwc. Perf. 3004'

Sanded hole back to 2975' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 20 sax mud, 2 sax hulls, & displaced

100 sax cement with Allied Cementing Company's pump truck, cementing

from 330' to base of cellar.

Very truly yours,

Don Leonard  
Conservation Division Agent