

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167 -21,864-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name V. Frances Weigel

Complete Address Z. Box 244 Gorham, Ks. 67640

Lease Name Weigel F.

Well No. 1

Location SW NW NW

Sec. 16 Twp. 13 Rge. 15 (East) (West)

County Russell

Total Depth 3330'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated

Plugging Contractor Sheilds Drilling Co. Inc.

Address Sheilds Bldg. Box 709 Russell, Ks. 67665

License No.

Operation Completed: Hour: 5:30 PM Day: 14 Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part STATE CORPORATION COMMISSION None

The above well was plugged as follows:

8 5/8" 691' S.P. cuc. W/ 350 sacks common 2% Gel-3% Cal.Cl.

Ordered 135 sacks 50/50 posmix 4% Gel-3% Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' W/ 70 sacks cement

2nd plug @ 310' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks cement in rat hole, and 5 sacks cement in mouse hole.

Amount of Surface Casing: 691' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

NOTICED

Signed:

Conservation Division Agent

WV. NO. 2-9-82
9382-W