

KANSAS

FORM CP-3  
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,732-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Isern-Schultz Oil & Gas, Inc.

Complete Address Box 486, Ellinwood, Kansas 67526

Lease Name Brungardt Well No. 1

Location SE NE SW Sec. 15 Twp. 13 Rge. 15 (~~East~~) (West)

County Russell Total Depth 3330'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Helberg Drilling Co. and Sun Oil Well Cementing Co.

Address Box 32, Morland, Kansas License No. \_\_\_\_\_

Operation Completed: Hour: 5:00 AM Day: 19 Month: June Year: 19 81

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows: 8-5/8"-222'-135 sacks Elev. 1866 GL  
Anhydrite 936-69'

Hole circulated and filled with mud. 50 sacks cement pumped through

drill pipe at 620'. 30 sacks cement pumped through drill pipe at 225'.

Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and

hole cemented to base of cellar with 10 sacks cement. Rathole cemented

with 10 sacks cement. Cement used: 50-50 Pozmix w/4% gel and 3% cal. chl.

RECEIVED

STATE CORPORATION COMMISSION

JUN 23 1981

CONSERVATION DIVISION

I hereby certify that the above well was plugged as herein stated. Wichita, Kansas

INVOICED

Signed: [Signature]  
Conservation Division Agent

DATE 7-27-81

INV. NO. 6100-W