

15-167-02077-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1974
10-21-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. F. Schmidt

Complete Address P. O. Box 662, Russell, Kansas 67665

Lease Name McKune Well No. # 4

Location SE NE SW Sec. 17 Twp. 13 Rge. 15 (E) (W) W

County Russell Total Depth 3306

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 2:30 P.M. Day 16 Month 10 Year 1974

The above well was plugged as follows:

8 5/8" csg. 595' Cwc. Perf. 3012'

Sanded hole back to 2975' & dumped 5 sax cement with dump bailer. Pulled pipe.

Squeezed well with 3 sax hulls, 20 sax mud, released plug, & displaced 100 sax

cement with Allied Cementing Company's pump truck, cementing from 330' to base

of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Don Lewis
Well Plugging Supervisor

INVOICED

DATE 10/23/74

INV. NO. 141-W