

15-167-06481-00-00

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten scribble]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SE

SEC. 22 TWP. 15 RGE. 15

Dry Hole Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Johnson

Operator Stearns Pet Co Address Russell, Kans

Field _____ County Russell

Total Depth 3374 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 266' circulated with cement - 4 1/2" at 3318' with
75 Sax cement behind - Lane wells plug set and perf at 3096'
Squeezed with 100 sax cement through perforations at 3116',
Filled hole with mud and chat to 3083', run 2 sax cement with
dump bailer - pulled 2590' of 4 1/2" - filled hole with heavy mud
to 260', set wood plug, rock bridge and 15 sax cement - filled
with heavy mud to 35' set wood plug, rock bridge and 10 sax
cement.

02-23-1950

[Signature]
District Conservation Agent

Date 2-18-50

PLUGGING
FILE SEC 22T-13R/SW
BOOK PAGE 139 LINE 40