

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- - 167-21,659-00-00

245 North Water  
Wichita, KS 67202

Operator's Full Name John O. Farmer, Inc.

Complete Address P. O. Box 352, Russell, Kansas 67665

Lease Name Olson "B" Well No. 1

Location NW NW NW Sec. 23 Twp. 13S Rge. 15 (~~EXXX~~) (West)

County Russell Total Depth 3318'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  XX

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Shields Drlg. Co., Inc. & Allied Cementing Co.

Address Shields Bldg., Russell, Kansas 67665 License No. \_\_\_\_\_

Operation Completed: Hour 7:30 Day 25 Month 3 Year 1981  
PM

The above well was plugged as follows:

Filled hole with mud and spotted 50 sx cement at 540'.

Filled hole with mud and spotted 30 sx cement at 240'.

Filled hole with mud to 40' and  $\frac{1}{2}$  sx hulls, plug, and  
10 sx cement to bottom of celler.

Filled rat hole with cement.

Filled mouse hole with cement.

211' of 8 5/8" surface casing cement circ.

RECEIVED  
CORPORATION COMMISSION

MAR 27 1981  
03-27-1981  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane Rankin  
Conservation Division Agent

DATE 4-23-81

NO. 5193-W