

15-167-05446-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 127-31

LOCATION SW SW SW

SEC. 23 TWP. 13 RGE. 15

Dry Hole ~~X~~ Abandoned Oil Well ~~X~~ ^{ANG} Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Dockendorf

Operator Alva Billings Address Russell, Kans

Field _____ County Russell

Total Depth 3323 Feet.

(Describe briefly the manner in which the well was plugged)

4 1/2" at 3315', top perforations at 2480', this was squeezed
with 100 sax, again with 100 sax again with 50 sax cement,
pipe shot off at 2460' with calseal on topshot, our measurements
with steel line stopped at 2357', run 2 sax cement at 2357
with dump bailer, pulled 1120' 4 1/2", filled hole with heavy
mud to 180', set rock bridge and 25 sax cement, filled with
heavy mud to 35', set rock bridge and 15 sax cement to bottom
cellar.

PLUGGING
FILE SEC. 23 T. 13 R. 15W
BOOK PAGE 127 LINE 31

Edon J. [Signature] ⁰³⁻⁰¹⁻¹⁹⁵⁰
District Conservation Agent
Date 2-24-50