

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-051-23769-0000

LEASE NAME Tanya

WELL NUMBER 2

1650 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 10 TWP. 11 RGE. 17 (E) or (W)

COUNTY Ellis

Date Well Completed 1-31-84

Plugging Commenced 10-29-93

Plugging Completed 10-29-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-29-93 (date)

by Dennis Hamel - Hays, KS (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Conglomerate Depth to Top 3344 Bottom 3374 T.D. 3675

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Conglomerate	Oil	3326	3394	8-5/8"	250	0
Lansing-KS	Oil	3042	3280	4 1/2"	3674	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from feet to feet each section. Pressure up to 300 psi on 8-5/8" X 4 1/2" casing held ok. Mix and pump 25 sks 60/40 Poz and 200# hulls followed by 18 bbl gel mud (6 sks gel) followed w/ 175 sks 60/40 Poz w/ 200# hulls. Maximum pressure = 950#. Shut in - pressure = 500psi. Cut off casing. Weld on plate. Backfill hole and recontour location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. _____

Address Hays, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Ken Jehlik (Employee of Operator Helmerich & Payne, Inc.)
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well as filed with the State Corporation Commission, and matters herein contained and the log of the above-described well as filed with the State Corporation Commission are true and correct, so help me God.

(Signature) Ken Jehlik AC

(Address) P.O. Box 558 Garden City, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 1993

Judy Richmeier
 Notary Public

My Commission Expires: August 15, 1996

RECEIVED
 STATE CORPORATION COMMISSION

NOV 04 1993