

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-23293-0000

LEASE NAME Tanya

WELL NUMBER 1

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 10 TWP. 11 RGE. 17 (X) of (W)

COUNTY Ellis

Date Well Completed 2-14-83

Plugging Commenced 10-29-93

Plugging Completed 10-29-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Helmerich & Payne, Inc.

ADDRESS P.O. Box 558 Garden City, KS 67846

PHONE#(316) 276-3693 OPERATORS LICENSE NO. 5293

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-29-93 (date)

by Dennis Hamel - Hays, KS (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Lansing-Kansas City Depth to Top 3120 Bottom 3346 T.D. 3425

and Conglomerate  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Conglomerate	Oil	3308	3353	8-5/8"	205	0
Lansing-KC	Oil	3028	3266	4 1/2"	3398	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material were used, state the character of same and depth placed, from    feet to    feet each section. Perforate casing at 1800', 1056', and 405'. Squeeze 4 1/2" production casing w/ 25 sks 60/40 Poz w/ 200# hulls followed w/ 18 bbls gel mud (6 sks gel) followed w/ 175 sks 60/40 Poz w/ 200# hulls. Maximum pressure = 650#. Pressured up on 8-5/8 X 4 1/2" casing annulus to 300# held ok. Cut off casing. Weld on cap. Recontour location.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address Hays, KS

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Helmerich & Payne, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

NOV 04 1993

Ken Jehlik (Employee of Operator) of (Operator) Conservation Division, Wichita, Kansas  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Ken Jehlik AC

(Address) P.O. Box 558 Garden City, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 93

John Richman  
Notary Public

My Commission Expires: August 15, 1996