

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County. Sec. 10 Twp. 11 Rge. 17 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner G. Ray Anderson et al

Lease Name Richmond Well No. 1

Office Address Topeka, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed September 9 1953

Application for plugging filed " " 1953

Application for plugging approved " " 1953

Plugging commenced " " 1953

Plugging completed " " 1953

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3371 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	137'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 55 sacks cement behind bottom cement plug, bottom plug stopped at 135', surface pipe was full of cement to bottom of cellar, cemented by Sun Oil Well Cementing Company, Hays, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn R. Nye Drilling Company,

Address Drawer 30, Hays, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
Glenn R. Nye (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye
Drawer 30, Hays, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of September, 1953

My commission expires May 9, 1957

John L. Spiess
Notary Public.

PLUGGING

FILE SEC 10 T 4 R 17 W
PAGE 129 LINE 44

09-18-53

Company: G. Ray Anderson
Contractor: Glenn R. Nye Drilling Company
Commenced: August 27, 1953
Completed: September 9, 1953

Farm: Richmond #1
Location: SE SE SE Sec. 10-11-17
Ellis County, Kansas
Casing Record: 8 5/8" set at 135'
Elevation: 1779 R.B.

(figures below indicate bottoms)

top soil & sand	40	
sand & gravel	80	
sand & shale	98	
shale	137	
shale	210	
sand	295	
red bed & shale	480	
shale	540	
shale & red bed	890	
shale & red bed	995	
anhydrite	1030	
shale & shells	1035	
shale	1260	
shale & shells	1550	
shale & shells	1650	
shale & lime streaks	1690	
lime & shale	1790	
lime & shale	1935	
lime & shale	2010	
lime & shale	2100	
lime & shale	2210	
lime & shale	2275	
lime & shale	2380	
lime & shale	2455	
lime & shale	2555	
lime & shale	2665	
lime & shale	2765	
lime & shale	2825	
lime & shale	2880	
lime & shale	2910	Heebner 2973 (-1176)
lime & shale	2970	Toronto 2991 (-1193)
lime & shale	3012	Lansing 3015 (-1218)
lime & shale	3020	
lime	3070	
lime	3110	
lime	3135	
lime	3150	
lime	3185	
lime	3220	
lime	3255	Conglomerate 3282 (-1485)
lime	3290	
cong. chert	3330	Simpson 3358 (-1561)
cherty lime	3345	Arbuckle 3365 (-1568)
lime	3365	
arbuckle	3371	T.D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

STATE OF KANSAS)
) SS
ELLIS COUNTY)

Subscribed to and sworn to before me, a notary public, in and for said County and State this 25th day of Sept. 1953.



John L. Shuess
Notary Public

My Commission Expires May 9, 1957

PLUGGING
FILE SEC 10-11-17W
BOOK PAGE 129 LINE 44