


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

6 copies 7-16-57  
15-051-00568-000



Locate well correctly on above Section Plat

Ellis County. Sec. 10 Twplls Rge. (E) 17 (W)  
Location as "NE/CNW&SW&" or footage from lines SW SW NE  
Lease Owner Tennessee Gas Transmission Company  
Lease Name Emma A. Richmond Well No. 1  
Office Address P.O. Box 163 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-13 19 57  
Application for plugging filed 7-15 19 57  
Application for plugging approved 7-13 19 57  
Plugging commenced 7-13 19 57  
Plugging completed 7-13 19 57  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3441 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	244	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud through drill pipe from TD. 3441 to 500'.  
Set plug @ 500' w/1/3 sack hulls. Cemented with 25 sax cement on top of plug.  
Filled with heavy mud to 40'.  
Set plug @ 40' w/1/3 sack hulls. Cemented w/10 sax cement on top of plug.  
Plugging completed 12:00 M 7-13-57

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shelley Miller Drilling Inc.  
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
Glen E. Armour (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X Glen E. Armour  
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of July, 1957

My commission expires May 20, 1958

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1957  
07-17-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 10 T. 11 R. 17W  
BOOK PAGE 28 LINE 34

Notary Public.

COMPANY: Tennessee Gas Transmission Company  
Chase, Kansas

Rotary Drilling Commenced: 7-1-57  
Rotary Drilling Completed: 7-13-57

LOCATION: Emma A. Richmond No. 1  
SW SW NE Sec. 10-11S-17W  
Ellis County, Kansas

CONTRACTOR: Shelley-Miller Drilling Company  
205 Miller Building  
Wichita, Kansas

CASING RECORD: 8 5/8 new 28 1/2 smls casing set @ 244', cemented  
with 175 sacks cement.

LOG

(Measurements from top of Rotary Bushing to bottom of formation)

Sand	18
Lime & Shale	130
Shale & Shells	245
Shale	458
Sand	705
Red Bed	1,043
Anhydrite	1,080
Shale & Shells	1,580
Lime & Shale	2,865
Lime	3,442 Rotary T. D.

The undersigned, Richard A. Shelley, Partner of Shelley-Miller Drilling Company, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING COMPANY

By Richard A. Shelley

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

BE IT REMEMBERED, that on this 19th day of July, 1957, before me, the undersigned, a Notary Public, duly commissioned in and for the county and state aforesaid, came Richard A. Shelley, Partner, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling Company, as a Partner of said company, and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

Leona M. Aowers  
Notary Public



PLUGGING  
FILE SEC. 10 T 11 R 17W  
BOOK PAGE 28 LINE 34