

#6

API NUMBER 15-051-24,124 -
 LEASE NAME CRESS 0000
 WELL NUMBER L
 SPOT LOCATION S/2 NW SW
 SEC. 13 TWP. 11 RGE. 17 or (W)
 COUNTY Ellis
 Date Well Completed 12-29-84
 Plugging Commenced 12-29-84
 Plugging Completed 12-29-84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR National Petroleum Reserves, Inc.
 ADDRESS 260 N. Rock Road, Suite 215 Wichita, KS 67202
 PHONE # (316) 681-3515 OPERATORS LICENSE NO. 9482

Character of Well D&A
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks.

to be filed by
 Is ACO-1 filed? operator If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3405

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Bottom Plug: @ 3375' w/25 sacks 50/50 pozmix 6% gel 3% cc. thru drill pipe
 Next Plug: @ 1075' w/25 " " " " " " " "
 Next Plug: @ 550' w/110 sacks " " " " " " " "
 Top Plug: @ 40' w/solid bridge of 1/2 sack Hulls & 10 sacks cement
 10 sacks cement in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929
 Address P.O. Box 823 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney

(employee of operator) of

~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Bill Draney CONSERVATION DIVISION
 Wichita, Kansas

(Address) Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 2nd day of Jan, 1984

Leahy M. Klague
 Notary Public

My Commission Expires: 4-29-86



DRILLER'S WELL LOG

DATE COMMENCED: December 19, 1984
 DATE COMPLETED: December 29, 1984

National Petroleum Reserves, Inc.
 CRESS #1
 C S/2 NW SW
 Sec. 13, T11S, R17W
 Ellis County, Ks.

ELEVATION: 1863 K.B.

0 - 253' Surface Soil, Post Rock, Shale
 253 - 1066' Shale w/sand streaks
 1066 - 1102' Anhydrite
 1102 - 2789' Lime & Shale
 2789 - 3023' Lime
 3023 - 3026' Shale
 3026 - 3039' Lime & Shale
 3039 - 3378' Lime
 3378 - 3405' RTD

FORMATION DATA

Anhydrite 1066'
 Topeka 2789'
 Heebner 3023'
 Toronto 3039'
 Lansing K.C. 3070'
 Arbuckle 3378'
 RTD 3405'

Surface Pipe: Set used 3-5/8"
 28# pipe @ 253' w/160 sacks
 50/50 pozmix 2% gel 3% cc.

AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON) ss

Bill Draney of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 2nd day of January 1985.

My Comm. Expires:

4-29-86

Dorothy M Hague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

JAN 08 1985

CONSERVATION DIVISION
 Wichita, Kansas