

15051-23769-0000

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-051-23769 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Helmerich & Payne, Inc. KCC LICENSE # 5293
(owner/company name) (operator's)

ADDRESS P.O. Box 558 CITY Garden City

STATE Kansas ZIP CODE 67846 CONTACT PHONE # (316) 276-3693

LEASE Tanya WELL# 2 SEC. 10 T. 11s R. 17 (East/West)

- SW - NW - SW SPOT LOCATION/QQQQ COUNTY Ellis

1650 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM E/(W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 250 CEMENTED WITH 160 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3674" CEMENTED WITH See reverse SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3344'-3374' Conglomerate

ELEVATION 1807' KB T.D. 3675' PBDT 3464 ANHYDRITE DEPTH 1036'
(G/A. (K.B.)) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Perforate salt at 1800', Anhydrite at 1056', and base of Dakota at 485'. Squeeze production perforations w/ 25 sks cmt w/ 100# hulls. Displace w/ 18 barrels mud w/ 6 sks gel spacer followed w/ 125 sks cmt w/ 200# hulls. Plugging (over)
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Leland Felthoelter PHONE# (913) 434-4667

ADDRESS P.O. Box 394 City/State Plainville, KS 67663

PLUGGING CONTRACTOR Halliburton KCC LICENSE #
(company name) (contractor's)

ADDRESS Hays, KS 67642 PHONE # (913) 625-3493

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9-15-93 AUTHORIZED OPERATOR/AGENT: Leland Felthoelter
(signature) A.C.

RECEIVED
STATE CORPORATION COMMISSION
KCC LICENSE #
(contractor's)
SEP 16 1993
9-16-93
CONSERVATION DIVISION
Wichita, Kansas

4)

Cement Detail

4½" Production casing set at 3647' and cemented w/ 174 sks. Squeeze cemented casing leak at 690' to 733'. February 1990 w/ 150 sks 60/40 Poz w/ 3% CaCl₂. 8-5/8" x 4½" annulus cemented w/ 350 sks 50/50 Poz w/ 6% gel and 6 sks hulls.

Plugging Procedure Continued

procedure per Dennis Hamil of KCC's Hays, Kansas office.

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

September 16, 1993

Helmerich & Payne Inc
P O Box 558
Garden City KS 67846

Tanya #2
API 15-051-23,769
1650 FSL 330 FWL
Sec. 10-11S-17W
Ellis County

Dear Leland Fellhoelter,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200