

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW SE NW

SEC. 9 TWP. 11 RGE. 17

Dry Hole    x    Abandoned Oil Well    Abandoned Gas Well   

I have this date completed supervision of plugging of:

Well No.   1   Lease   Carmichael  

Operator   Bankoff <sup>+ Leben</sup> Oil Co   Address   P.O. Box <sup>P.O. Box</sup> Drawer 2479   Tulsa, Okla

Field \_\_\_\_\_ County   Ellis  

Total Depth   3502   Feet.

Plugging Contractor   Leben Drg Co & Sun Cementing Co  

Plugging Contractor's License No. \_\_\_\_\_

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

  8 5/8" at 330', circulated with cement.  

  Gunned pits, circulated hole with heavy mud, set cementing plug at  

  500', displaced 25 sax cement through drill pipe, heavy mud to  

  300', set cementing plug, displaced 25 sax cement through drill pipe,  

  heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax  

  cement to bottom cellar.  

  Sun Cementing Co's pump truck.  

  *Leon Petty*    
District Conservation Agent

Date   8-2-57  

PLUGGING  
FILE SEC   9   T   11   R   17W    
BOOK PAGE   34   LINE   20  

RECEIVED  
STATE CORPORATION COMMISSION  
  08-06-57    
  AUG 6 1957    
CONSERVATION DIVISION  
Wichita, Kansas