

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1962
10-16-62
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Raymond Oil Co

Complete Address: 410 4th Natl Bk Bldg Wichita, Kansas

Lease Name Carmichael Well No. 2

Location CS $\frac{1}{2}$ NE SW Sec. 9 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3429

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling

Address: Great Bend, Kans License No. 399

Operation Completed: Hour 9AM Day 11 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 1099' circulated with cement - 5 1/2" 3426' with 150 sax cement
PB to 3417' perf 3342'.

3325'

Filled with sand to ~~3342'~~ set 4 sax cement with dump bailer, pulled 2796'
5 1/2" to 400', circulated hole with heavy gel mud through 5 1/2"- displaced 25
sax cement through 5 1/2" at 400', heavy mud to 170', displaced 20 sax cement
through 5 1/2" at 170', heavy mud to 35', set bridge and 10 sax cement to
bottom cellar.

Mudding and cementing by Southwest Company pump .

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edon Perry*
Well Plugging Supervisor

DATE 10/18/62

INV. NO. 5850-W