

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company

Complete Address 217 N. Water Wichita, Kansas

Lease Name C. E. Simpson Well No. 1

Location SW SW SE Sec. 9 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3367'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Bex 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 1:30 P Day 10 Month 9 Year 1971

The above well was plugged as follows:

Total Depth 3367' 8 5/8 csg set at 840' cwc

5 1/2 csg set at 3362' cw 100 sk cmt.

5 1/2 csg PBTD 3340' with top perf. (3050)

Set 5 1/2 wood plug at 3000' -peured sd & dumped 5 sk cmt W/dump bailer. (3250-3300)

Cutoff and recovered 1825' of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water W/200 lbs hulls, - release plug and

pumped 120 sk 60-40 poz 2% gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben F. Massey
Well Plugging Supervisor

DATE 9-14-71

INV. NO. 4319-W