

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1962
CONSERVATION DIVISION
WICHITA, KANSAS

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis

Location: SE NW SE Sec. 10 Twp. 11 Rge. _____ (E) _____ (W) 17

Name of Field: _____ Total Depth: 3385

I have this date completed supervision of plugging of:

Lease Name: Richmond Well No. 1

Operator's Full Name: Woodman & Iannitti

Complete Address: 714 Union Natl Bk Wichita, Kansas

Plugging Contractor Ace Pipe Pulling Co

Address: Great Bend, Kans License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 8 Month 4 Year 62

The above well was plugged as follows:

8 5/8" 171' circulated with cement - 5 1/2" 3379' with 75 sax cement.

Filled with sand to 3360', set 4 sax cement with dump bailer, pulled

2980' 5 1/2" to 700' - circulated hole with heavy mud at 700' - (28 sax weight

mud and 17 sax Gel) - pulled 5 1/2" to 325', displaced 20 sax cement through

5 1/2" at 325', heavy mud to 150', displaced 20 sax cement through 5 1/2" at 150',

heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Ace Company pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 4/19/62

INV. NO. 4840-w