

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 115-32

LOCATION NE NW SW

SEC. 10 TWP. 11 RGE. 17 W

Dry Hole Abandoned Oil well x Abandoned Gas well

I have this date completed supervision of plugging of:

Well No. 1 Lease Simpson

Operator G. Ray Anderson Address Box 53 Topeka, Kans

Field County Ellis

Total Depth 5390 Feet.

Plugging Contractor Pipe Pullers Inc

Plugging Contractor's License No.

Address Stafford, Kans

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1027' circulated with 500 sax cement - 5 1/2" at 3589' with
100 sax cement behind - Lane Wells plugs to ? - perforations at 3112' -
Set bridging plug at 3100', sand and 4 sax cement set with dump bailer-
pulled 2550' 5 1/2" - pumped hole full commercial mud (25) sax - pumped
cementing plug to 250', followed by 80 sax cement filling hole from
250' to 0' with cement - pump pressure 600#.

Mudding and Cementing by Sun Cementing Co.

PLUGGING
FILE SEC 10 T 11 R 17W
BOOK PAGE 115 LINE 32

RECEIVED
RCD
07-30-53
DISTRICT CONSERVATION DIVISION
WICHITA, KANSAS

Edgar Petty
District Conservation Agent

Date 7-28-53