

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 96-31

LOCATION SW NW SW

SEC. 13 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Crest~~ Cress

Operator West Supply Co Address Chase, Kans

Field Bemis County Ellis

Total Depth 5363 Feet.

(Describe briefly the manner in which the well was plugged)

13" at 60' circulated with cement - 8 5/8" at 1052' circulated  
with cement - 5 1/2" at 3359' with 100 sax cement behind.

Filled with chat to 3350', set 4 sax cement with dump bailer,  
pulled 2600' 5 1/2", filled hole with mud to 250', set rock  
bridge and 20 sax cement, filled with mud to 35', set rock and  
10 sax cement to bottom cellar.

**PLUGGING**  
FILE SEC 13 T 11 R 17  
BOOK PAGE 96 LINE 31

*E. J. [Signature]*  
District Conservation Agent  
Date 8-1-51  
RCWD 08-06-51