

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sinclair Oil & Gas

Complete Address: R R # 1 Great Bend, Kansas

Lease Name Cross Well No. 2

Location SE SE NE Sec. 13 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3343

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 7PM Day 10 Month 9 Year 63

The Above well was plugged as follows:

16" 104' circulated with cement - 9 5/8" 1020' with 450 sax cement - 7"
3331' with 100 sax cement & squeezed at 2600' with 450 sax cement.

Sand back & calseal plug at 3288' - pull 13d 1500' 7" casing - pumped hole
with heavy gel mud to 450', set 20 sax cement at 450' - heavy gel mud to
180', set 20 sax cement at 180' - heavy gel mud to 30' - cement 30' to 0'

Mudding and cementing by Knight Company Pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/12/63
INV. NO. 7734-u

Signed: *Leden Petty*
Well Plugging Supervisor