

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 19 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Larie Oil & Gas Company

Complete Address 301 South Market, Wichita, Kansas 67202

Lease Name F. Cress Well No. 2

Location NW SW SW Sec. 13 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3377'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 9:30 A Day 17 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3377' 8 5/8 csg set at 1064' cwc 335 sk.

5 1/2 csg set at 3362' cw 150 sk.

Filled 5 1/2 csg W/sd (3377-3340) dumped 4 sk cmt W/dump bailer. (3340-3310)

Cutoff and recovered 2675' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 480' Oset rock & sand bridge (480'-470')

Filled with readymix cement from 470' to base of collar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 8/19/74  
INV. NO. 9721-W

Signed: Leo J. Massey  
Well Plugging Supervisor