

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW NE NE

SEC. 13 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease ~~Kress~~ Cress AUB KCC

Operator Lario Oil & Gas Address Wichita, Kans

Field Bemis County Ellis

Total Depth 5338' Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 1007' circulated with cement - 7" at 5335' with
120 sax cement behind.

Lane Wells plugs to 2995', perforations at 2972'

Filled with sand to 2965', set 5 sax cement with dump bailer,

pulled 2700' 7", filled hole with mud to 300', set rock and

25. sax cement, mud to 35', set rock and 10 sax cement to

bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1952
10-14-52
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent
Date 10-12-52

PLUGGING
FILE SEC. 13 T. 11 R. 17
BOOK PAGE 52 LINE 10