

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SW NE

SEC. 13 TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Gress _____

Operator West Supply Co. Address Great Bend, Kans. Chase, Kans

Field Bemis County Ellis

Total Depth 3363 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 707' circulated with 350 sax cement - 5 1/2" at 3361' with 100 sax cement behind.

Filled with chat to 3355', set 4 sax cement with dump bailer, pulled 5 1/2" - hole filled with mud - pumped in Halliburton plug followed by 80 sax cement - cement from 320' to 80', mud 80' to 25', cement 25' to 0'

PLUGGING RECEIVED
FILE SEC 13 T 11 R 17
BOOK PAGE 28 LINE 32
JUL 10 1952
CONSERVATION DIVISION
Wichita, Kansas

E. J. [Signature]
District Conservation Agent
Date 7-7-52