

KANSAS CORPORATION COMMISSION ONE POINT STABILIZED OPEN FLOW OR DELIVERABILITY TEST

Type Test:

- Open Flow
 Deliverability

(See Instructions on Reverse Side)

Test Date:

API No. 15
023-20595-0000

Company LOBO PRODUCTION, INC.		Lease RUEB-FARMS			Well Number 6-2
County CHEYENNE	Location W/2-NE-NE	Section 2	TWP 5S	RNG (E/W) 42W	Acres Attributed
Field CHERRY CREEK NIOBRARA		Reservoir NIOBRARA		Gas Gathering Connection LOBO PRODUCTION, INC.	
Completion Date 9-25-04		Plug Back Total Depth 1425'		Packer Set at	
Casing Size 4.5	Weight 13.5#	Internal Diameter	Set at 1438'	Perforations 1298'	To 1334'
Tubing Size	Weight	Internal Diameter	Set at	Perforations	To
Type Completion (Describe) SINGLE GAS		Type Fluid Production		Pump Unit or Traveling Plunger? Yes / No NO	
Producing Thru (Annulus / Tubing) CASING		% Carbon Dioxide		% Nitrogen	
Vertical Depth(H) TD - 1445'		Pressure Taps		(Meter Run) (Prover) Size 4" METER RUN	
Pressure Buildup:	Shut in <u>10 / 18</u> 20 <u>04</u> at <u>8:00</u> (AM) (PM)	Taken <u>10 / 21</u> 20 <u>04</u> at <u>8:00</u> (AM) (PM)			
Well on Line:	Started <u>10 / 21</u> 20 <u>04</u> at <u>8:00</u> (AM) (PM)	Taken <u>10 / 23</u> 20 <u>04</u> at <u>9:00</u> (AM) (PM)			

OBSERVED SURFACE DATA

Duration of Shut-in 72 Hours

Static / Dynamic Property	Orifice Size (inches)	Circle one: (Meter) or Prover Pressure psig (Pm)	Pressure Differential in Inches H ₂ O	Flowing Temperature t	Well Head Temperature t	Casing Wellhead Pressure (P _w) or (P _i) or (P _c)		Tubing Wellhead Pressure (P _w) or (P _i) or (P _c)		Duration (Hours)	Liquid Produced (Barrels)
						psig	psia	psig	psia		
Shut-in	.875	254				254	267.5			72	0
Flow	.875	62	6	52	62	62	75.5			49	0

FLOW STREAM ATTRIBUTES

Plate Coefficient (F _v) (F _p) Mcfd	Circle one: (Meter) or Prover Pressure psia	Press Extension $\sqrt{P_m \times h}$	Gravity Factor F _g	Flowing Temperature Factor F _t	Deviation Factor F _{pv}	Metered Flow R (Mcfd)	GOR (Cubic Feet/ Barrel)	Flowing Fluid Gravity G _m
4.606	75.5	21.28	1.0	1.0	1.0	98.03	N/A	N/A

(OPEN FLOW) (DELIVERABILITY) CALCULATIONS

(P_c)² = 71.56 ; (P_w)² = 5.70 ; P_d = _____ % (P_c - 14.4) + 14.4 = _____ ; (P_a)² = 0.207 ; (P_d)² = _____

(P _c) ² - (P _a) ² or (P _c) ² - (P _d) ²	(P _c) ² - (P _w) ²	Choose formula 1 or 2: 1. P _c ² - P _a ² 2. P _c ² - P _d ² divided by: P _c ² - P _w ²	LOG of formula 1. or 2. and divide by: $\frac{P_c^2 - P_w^2}{P_c^2 - P_a^2}$	Backpressure Curve Slope = "n" or Assigned Standard Slope	n x LOG	Antilog	Open Flow Deliverability Equals R x Antilog (Mcfd)
71.353	65.860	1.083	.035	.850	.029	1.070	104.89

Open Flow **104.89** Mcfd @ 14.65 psia Deliverability Mcfd @ 14.65 psia

The undersigned authority, on behalf of the Company, states that he is duly authorized to make the above report and that he has knowledge of the facts stated therein, and that said report is true and correct. Executed this the 12 day of November, 20 04.

Witness (if any)

For Commission

For Company

Checked by

RECEIVED
NOV 15 2004
KCC WICHITA

John Lardner
For Company

I declare under penalty of perjury under the laws of the state of Kansas that I am authorized to request exempt status under Rule K.A.R. 82-3-304 on behalf of the operator LOBO PRODUCTION, INC. and that the foregoing pressure information and statements contained on this application form are true and correct to the best of my knowledge and belief based upon available production summaries and lease records of equipment installation and/or upon type of completion or upon use being made of the gas well herein named.


I hereby request a one-year exemption from open flow testing for the RUEB-FARMS 6-2 gas well on the grounds that said well:

(Check one)

- is a coalbed methane producer
- is cycled on plunger lift due to water
- is a source of natural gas for injection into an oil reservoir undergoing ER
- is on vacuum at the present time; KCC approval Docket No. _____
- is not capable of producing at a daily rate in excess of 250 mcf/D

I further agree to supply to the best of my ability any and all supporting documents deemed by Commission staff as necessary to corroborate this claim for exemption from testing.

Date: 11 / 12 / 04

Signature: 
Title: OWNER/OPERATOR

Instructions: If a gas well meets one of the eligibility criteria set out in KCC regulation K.A.R. 82-3-304, the operator may complete the statement provided above in order to claim exempt status for the gas well.

At some point during the current calendar year, wellhead shut-in pressure shall have been measured after a minimum of 24 hours shut-in/buildup time and shall be reported on the front side of this form under **OBSERVED SURFACE DATA**. Shut-in pressure shall thereafter be reported yearly in the same manner for so long as the gas well continues to meet the eligibility criterion or until the claim of eligibility for exemption **IS** denied.

The G-2 form conveying the newest shut-in pressure reading shall be filed with the Wichita office no later than December 31 of the year for which it's intended to acquire exempt status for the subject well. The form must be signed and dated on the front side as though it was a verified report of annual test results.