

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22506-00-00
Spot: NESE Sec/Twnshp/Rge: 36-33S-39W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: BANE Well #: 36 1
County: STEVENS Total Vertical Depth: 6425 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5650		WITH 2 SX CMT
SURF	8.625	1665		WITH 210 SX CMT
PROD	4.5	6425	2295	WITH 220 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/23/2010 8:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUG PER KCC GUIDELINES AND REGULATIONS WHICH MAY INCLUDE: LOAD CSG W/ MUD, SET CIBP @ 5650' AND CAP W/2 SKS CMT, CUT ANDP ULL FREEPIPE, MIX AND SPOT 1Q20 SKS CMT 1715-1276', MIX AND SPOT 50 SKS CMT 600', TOP OUT 64-4 W/20 SKS CMT, DIGOUT/CUT OFF 4/ BGL AND WELD ON ID PLATE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/24/2010 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5650' WITH 2 SX CMT. PLUG AT 1715' WITH 120 SX CMT. PLUG AT 630' WITH 80 SX CMT. NO CIRCULATION. SHUT IN FOR 2 HOURS. TAGGED TOC @ 1650'. RIH W/TBG TO 1650' & PUMPED 50 SX CMT. NO CIRCULATION. SDON. 6/24/10: TAGGED TOC @ 910'. PUMPED 50 SX CMT AT 630' WITH GOOD CIRCULATION. PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6236	6248		
5911	5917		KEYES
5768	5804		MORROW
5700	5760		MORROW

INVOICED
DATE 10-14-2010
INV. NO. 2011060042

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 06 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLuskey
(TECHNICIAN)

RECEIVED

JUN 30 2010

KCC DODGE CITY