

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21016-00-00  
Spot: NWSWSWNW Sec/Twnshp/Rge: 19-20S-9W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: F MALONE Well #: 2  
County: RICE Total Vertical Depth: 3382 feet

Operator License No.: 33725  
Op Name: FOUNDATION ENERGY MANAGEMEN  
Address: 14800 LANDMARK BLVD STE 220  
DALLAS, TX 75254

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		175 SX
PROD	4.5	3381		75 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/18/2010 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: KENT STRUBE Company: FOUNDATION ENERGY MGMT Phone: (620) 786-4161

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 06/18/2010 10:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1250', 850', AND 260'. RUN TUBING TO 3280' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 1250' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 850' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 260' AND CIRCULATE CEMENT TO SURFACE. SHUT VALVE ON 4.5" AND CIRCULATE CEMENT OUT OF SURFACE CASING. PULL TUBING OUT AND TOP OFF. USED 220 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
3331	3342	CSG	

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060046

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 06 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL UNLESS OTHERWISE SPECIFIED. GRESSELL OILFIELD SERVICE. PERF TICKET 0724. COPELAND CEMENT #V36528.

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

*1/2*