

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-19008-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 23-9S-21W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: LANSING KANSAS CITY UNIT Well #: 14  
County: GRAHAM Total Vertical Depth: 3772 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1664	0	w/650 sxs cmt
PROD	5.5	3769	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2010 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 500 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Perfed at 1650' - 990' - 250'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/29/2010 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Tubing to 2008' - pumped 265 sxs 60/40 pozmix - 4% gel with 525# hulls.  
Pulled tubing to 1000' - pumped 125 sxs 60/40 pozmix - 4% gel with 150# hulls to circulate to surface.  
Pulled all tubing. Hooked to 5 1/2" casing - pumped 50 sxs 60/40 pozmix - 4% gel to circulate out 8 5/8" annulus.  
S.I.P. 300# on 5 1/2" casing and 8 5/8" annulus.

Perfs:

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060050

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUL 02 2010  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT CEMENTING COMPANY-TICKET #18022. LEASE ORIGINALLY KNOWN AS BALTHAZOR #2.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

Pat Bedore  
(TECHNICIAN)

CM

JUN 30 2010

double-click in this window to close it

BUTIRAM PETROLEUM CORP #2 BATHAZOR 23-9-21W  
NW NW NE

Contr. GRAHAM County

E. 2269 Comm 2-23-44 Comp 4-11-44 IP 3000 BOPD  
DEPTH

Top	Depth	Datum
ASH	1750	
ARB	3768	
TD	3773	

Casing  
 8" 1664  
 5" 3773  
  
 1000' OIH/40"  
 Swb 38 BOPH/5 hrs  
 A/1000


INDEPENDANT OIL & GAS SERVICE  
WICHITA, KANSAS