

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02933-00-00
Spot: NENWNE Sec/Twnshp/Rge: 23-9S-21W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: LANSING KANSAS CITY UNIT Well #: 15
County: GRAHAM Total Vertical Depth: 3771 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	217	0	150 SX
L1	4.5	3424	0	w/200
PROD	6.625	3767	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/28/2010 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 550# hulls.
Perfed 990' and 1750'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 06/28/2010 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2008' - pumped 170 sxs 60/40 pozmix - 4% gel with 250# hulls.
Pulled tubing to 1000' - pumped 60 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled all tubing. Hooked to 4 1/2" casing - pumped 35 sxs 60/40 pozmix - 4% gel.
S.I.P. 400#.
Hooked to 10 3/4" x 6 5/8" annulus - pumped 40 sxs 60/40 pozmix - 4% gel.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3648	3653		LKC
3629	3633		LKC
3587	3591		LKC
3542	3547		LKC
3535	3539		LKC
3460	3466		LKC

INVOICED
DATE: 10-14-2010
NW NO. 2011060050

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 02 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT CEMENTING COMPANY-TICKET #17680. LEASE ORIGINALLY KNOWN AS BALTHAZOR #6.

Plugged through: TBG

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

MAGNOLIA PETROLEUM CO. #6 BALTHAZOR

23-9-21W
NE NW NE

Contr. BARNETT DRILLING, INC. GRAHAM County

E. 2264 Comm. 2-24-49 Comp. 4-1-49 IP 116 BOPD & 3 BW

Tops	Depth	Datum
LANS	3443	-1179
SIMP	3739	-1475
ARB	3767	-1503
T.D.	3771	-1507

Casing

10" 217 SWB 5 BOPH/6 HRS
6" 3767 PMP 30 BO/8 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS
