

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15073-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 30-16S-11W  
990 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SOUTH OESER Well #: 7  
County: BARTON Total Vertical Depth: 3295 feet

Operator License No.: 4871  
Op Name: HITSCHMANN, CURTIS LEE DBA CURT  
Address: PO BOX 328  
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	313	0	w/unknown sxs cmt
PROD	5.5	3260	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/21/2010 2:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CURT'S OIL OPERATIONS Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Old well had been covered. Dug up well - rendered well bore bridged at 320' - drilled through bridge - went to 1200' - tubing in the hole at 1200' - could not get past.  
Decided to plug from there.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2010 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 1200' - circulated cement to surface with 160 sxs cement.  
Pulled tubing - tied onto backside - pumped 15 sxs cement.  
Max. P.S.I. 150#. Shut in.  
Tied to casing and pumped 20 sxs.  
Max. P.S.I. 150#. Shut in.

Perfs:

Top	Bot	Thru	Comments
3260	3272		
3123	3128		

INVOICED  
DATE: 10-14-2010  
INV. NO. 2011060053

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

RECEIVED

JUL 29 2010

Form CP-2/3

JUL 27 2010

KCC WICHITA

S. A. SPRINGER ET AL

#7

OESER

30-16-11W / 53  
NW SW SW


Contr. \_\_\_\_\_ BARTON \_\_\_\_\_ County

E. 1913 Comm. \_\_\_\_\_ Comp. 11-17-50 IP 107 BOPD

Tops	Depth	Datum
ANH	750	+1163
TOP	2687	- 774
HEEB	2927	-1014
BR LM	3022	-1109
LANS	3036	-1123
QTZ	3260	-1347
T.D.	3295	-1382

Casing  
 8" 313 PERF 326-72, PB 3180  
 5" 3260 PERF 3123-28  
 SWB 3 1/2 BOPH

KRAFT PRUSA POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS