

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10164-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 6-27S-12W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HELMKE J ICHU Well #: 5
County: PRATT Total Vertical Depth: 4270 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1460		WITH 2 SX CMT
CIBP		2740		WITH 2 SX CMT
CIBP		2910		
SURF	8.625	427		WITH 250 SX CMT
PROD	5.5	4210	0	PBTD @ 2910

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/07/2010 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SET CIBP @ 2740' & 1460'. PUT 2 SX CMT ON TOP OF WACH CIBP. PERFORATE 5 1/2" @ 720'. CIRCULATE CMT FROM 720' TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/08/2010 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2740' & 1460'. PUT 2 SX CMT ON TOP OF EACH CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" CASING @ 720'. PUMPED DOWN 5 1/2" CASING WITH 300 SX CMT. HAD GOOD TO POOR RETURNS UP 5 1/2" X 8 5/8" ANNULUS. DID GET SOME CMT COLORED WATER AT TAIL END OF THE 300 SX CMT. WENT ON VACUUM. SHUT DOWN TO LET CMT SET. 7/8/10: TAG TOP OF CMT INSIDE 5 1/2" @ 195'. WAIT ON CMT. TOPPED OFF 5 1/2" CASING WITH 20 SX CMT. PUMPED DOWN 5 1/2" X 8 5/8" ANNULUS WITH 5 SX CMT. PRESSURED TO 300#. SHUT IN.

Perfs:

Top	Bot	Thru	Comments
2910	2910		
2782	2790		

INVOICED

DATE 10-14-2010

INV. NO. 2011060054

RECEIVED

JUL 21 2010

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

JUL 14 2010

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)