

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20168-00-00
Spot: SENW Sec/Twnshp/Rge: 7-33S-31W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease Name: GRABER Well #: 1
County: SEWARD Total Vertical Depth: 5973 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		WITH 2 SX CMT
SURF	8.625	1567		WITH 700 SX CMT
PROD	5.5	5973	2231	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/15/2010 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: SET CIBP @ 4300' & DUMP 2 SXS CMT ON TOP. CUT & PULL 5 1/2" CSG @ 1500'. SPOT 50 SX CMT PLUG @ 1500'. SPOT 50 SX CMT PLUG @ 630'. CMT FROM 40' TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/16/2010 11:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4300' WITH 2 SX CMT. 1ST PLUG AT 1590' WITH 50 SX CMT. 2ND PLUG AT 630' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5952	5956		
5624	5628		
4406	4414		

INVOICED
DATE 10-14-2010
INV. NO. 2011060056

RECEIVED

JUL 26 2010

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
JUL 22 2010
KCC DODGE CITY