

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20716-00-00
Spot: SWSENE Sec/Twnshp/Rge: 23-29S-41W
1150 feet from N Section Line, 510 feet from E Section Line
Lease Name: ARNOLD Well #: 23-2
County: STANTON Total Vertical Depth: 5950 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: PO BOX 1330 REGULATORY GROUP
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5610		
SURF	8.625	1619		WITH 550 SX CMT
COND	20	40		WITH 4 YDS CMT
DVT		3400		WITH 550 SX CMT
PROD	5.5	5949	0	WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/28/2010 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX CMT. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 600' WITH 40 SXC M.T 10 SX CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2010 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

1ST PLUG PUMP 400# HULLS & 25 SX CMT AT 5436'. 2ND PLUG AT 1650' WITH 25 SX CMT. TAGGED TOC @ 1430'. 3RD PLUG AT 650' WITH 25 SX CMT. SHOT OFF CASING AT 375'. PULLED 5' & CASING STACKED OUT. PUMPED 40 SX CMT INTO 5 1/2" X 8 5/8" ANNULUS. FILLED TO SURFACE. 4TH PLUG PUMPED 20 SX CMT INSIDE 5 1/2" CASING. FILLED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5469	5479		
5452	5456		
5445	5447		
5420	5430		

INVOICED
DATE 10-14-2010
INV. NO. 2011060058

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 06 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED

JUN 30 2010

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)