

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-00551-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 30-31S-40W  
1650 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: SWINDLER Well #: 1  
County: MORTON Total Vertical Depth: 2268 feet

Operator License No.: 33002  
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP  
Address: PO BOX 1330 REGULATORY GROUP  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	558		WITH 400 SX CMT
PROD	5.5	2256	735	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2010 11:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 30 SX CMT & 300# HULLS. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/06/2010 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG PUMP 45 SX CMT @ 2000' THROUGH TBG. HOLE CIRCULATED. 2ND PLUG PUMP 70 SX CMT & 150# HULLS @ 600'. WAIT 2 HOURS. TAG PLUG @ 340'. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2256	2268	OH	
2176	2196		

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060058

RECEIVED  
JUL 23 2010

KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)

RECEIVED  
JUL 14 2010  
KCC DODGE CITY

Form CP-233