

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20755-00-00
Spot: S2NESESE Sec/Twnshp/Rge: 8-29S-41W
740 feet from S Section Line, 330 feet from E Section Line
Lease Name: WARD Well #: 8-1
County: STANTON Total Vertical Depth: 5970 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: PO BOX 1330 REGULATORY GROUP
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5250		WITH 2 SX CMT
CIBP		5410		
SURF	8.625	1649		WITH 550 SX CMT
DVT		3432		WITH 630 SX CMT
PROD	5.5	5969	0	WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/30/2010 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT ON BOTTOM IF FLUID LEVEL IS LOW. LOAD WITH MUD. RUN BOND LOG FROM 1675-0'. PLUG AT 1650' WITH 25 SX CMT. PLUG AT 600' WITH 25 SX CMT, PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2010 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 5250' WITH 2 SX CMT. RAN BOND LOG. TOC @ 380'. TIH WITH TBG TO 1650'. PLUG AT 1650' WITH 25 SX CMT. PLUG AT 600' WITH 25 SX CMT. PLUG AT 40' WITH 5 SX CMT. FILL ANNULUS WITH 7 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5425	5432		
5318	5328		

INVOICED
DATE 10-14-2010
INV. NO. 2011060058

RECEIVED
JUL 23 2010

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

KCC WICHITA

District: 01

RECEIVED

JUL 13 2010

KCC DODGE CITY

Signed

Ken Jehlik
(TECHNICIAN)

[Signature]