

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25334-00-00
Spot: SENWNW Sec/Twnshp/Rge: 3-19S-15W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: RABEN Well #: 1-3
County: BARTON Total Vertical Depth: 3699 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	967	0	200 SX
PC		2044		125 SX
PROD	5.5	3696	2400	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2010 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed
Plugging
Method:

Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/14/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2400' - pulled casing to 1507' - pumped 125 sxs cement with 200# hulls.
Pulled casing to 975' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 500' - pumped 50 sxs cement with 100# hulls.
Pulled casing to 250' - circulated cement to surface with 70 sxs cement.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3580	3588		

INVOICED
DATE 10-14-2010
INV. NO. 2011060061

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

CM

RECEIVED

(TECHNICIAN)

JUL 19 2010

KCC WICHITA

Form CP-2/3

JUL 15 2010

Replacement Card

L D DRILLING
GREAT BEND KS 67530-6525

3-19S-15W
SE NW NW
KANSAS

#1-3 RABEN

City: BARTON
Site: 1-1/4 S & 1-3/4 E OF ALBERT KS
Field: OTIS-ALBERT

Spot: C SE NW NW API 15-009-25334
Lat/Long: 38.43179 -98.97427

TEMP ABD

FR: 07/31/2009 Spd: 09/17/2009 Drig Cp: 09/24/2009 Issued: 02/08/2010 Revised: 03/22/2010

Copyright 2010 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

TEMP ABD, 3/1/2010

Revisions: CORR & INFO REL: 3/22/2010 - WAS OIL
WELL IN ERROR; WAS TIGHT HOLE

Notes: CORR 9/17/2009 - ORIG FR AS L D DRILLING #1
AS CONTR

Contr: PETROMARK DRILLING #2

Geot: KIM B. SHOEMAKER

Elev: 1990 KB, 1985 GL, 1988 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

L ANH	962 +1028
L CHASE	1847 +143
L WINF	1900 +90
L NEVA	2352 -362
L STOT	2692 -702
L TARK	2750 -760
L HOW	2890 -900
L TOP	2964 -974
L HEEB	3208 -1218

L BR LM	3281 -1291
L LANS	3288 -1298
L BKC	3510 -1520
L ARB	3594 -1604
L REAGAN SD	3602 -1612
L GRAN WSH	3654 -1664
PBTD	3674 -1684
LTD	3699 -1709
RTD	3699 -1709

Csg: 8-5/8" 967 / 375 SX (ALT 1), 5-1/2" 3696 / 125 SX,
PORT COLLAR AT 2044.09 / 125 SX

Find:

COMMENT: PROPOSED START 9/1/2009; MI &
RURT 9/17/2009

NO CORES

DST(1) 1816-1880 (CHASE) 30-45-45-60, (1ST
OP) SB OFF BTM BKT/14", (2ND OP) SB OFF BTM
BKT/21", REC 60' V SLI W & GCM (2% W, 3% G,
95% M) ISIP 217# FSIP 187# IFP 31#-62# / FFP
69#-83# BHT 85°