

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25348-00-00
Spot: W2NENWNE Sec/Twnshp/Rge: 1-19S-15W
4950 feet from S Section Line, 1850 feet from E Section Line
Lease Name: REIFSCHNEIDER Well #: 2
County: BARTON Total Vertical Depth: 3561 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	904	0	210 SX
DVT		1999		150 SX
PROD	5.5	3554	1700	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2010 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 1700' - pulled to 1500' - pumped 125 sxs cement with 200# hulls.
Pulled to 975' - pumped 50 sxs cement with 100# hulls.
Pulled to 500' - pumped 150 sxs cement with 100# hulls - circulated to surface.
Pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
1812	1820		
1794	1804		

INVOICED
DATE 10-14-2010
INV. NO. 2011060061

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

RECEIVED

JUL 29 2010

Form CP-2/3

KCC WICHITA

JUL 27 2010

L D DRILLING
GREAT BEND KS 67530-6525

#2 REIFSCHNEIDER

1-19S-15W
130°W, C N/2 NE NW
KANSAS

City: BARTON
Site: 1 S & 3-3/4 E OF ALBERT KS
Field: MARTEN NE

Spot: W2 NE NW NE API 15-009-25348
Lat/Long: 38.43342 -98.92890

D&A

FR: 09/23/2009 Spd: 01/26/2010 Drig Cp: 02/01/2010 Issued: 07/12/2010 Revised: 07/12/2010

Copyright 2010 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:

D&A, ARB, 5/1/2010

Notes: CORRECTION 1/26/2010 - ORIG FR AS L D

DRILLING #1 AS CONTR

Contr: PETROMARK DRILLING #2

Elev: 1929 KB, 1924 GL, 1927 DF

Formation Tops: (L-Log, S-Sample, D-Driller)

NO TOPS RPTD

PBTD

1999-70

RTD

3561-1632

Csg: 8-5/8" 904 / 365 SX (ALT 1), 5-1/2" 3554 / 150 SX

Finds:

COMMENT: WAS ABD LOC, EXPIRED PERMIT

(FR 10/15/2007, API 15-009-25348); PROPOSED

START 10/5/2009; MI & RURT 1/26/2010

NO CORES

DSTS TAKEN - DETAILS NA

Comp Info: TRGT ZN: ARB (OIL), PTD 3620 (ARB),

MICT - CO, PF (FORM & INTV NA), NON-PROD, PB

1999, SI - EVAL FOR P & A (APPL FILED 4/23/2010)
- TIGHT HOLE - NO OTHER INFO AVAILABLE -
TEMP COMP 7/12/2010