

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21848-00-00
Spot: S2SWNE Sec/Twnshp/Rge: 19-14S-31W
2285 feet from N Section Line, 2031 feet from E Section Line
Lease Name: THIES RANCH Well #: 3-19
County: GOVE Total Vertical Depth: 4530 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 228 | | |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/01/2010 11:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: LARRY Company: LARIO OIL & GAS COMPANY Phone: (316) 265-5611

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 07/01/2010 12:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 2270' w/25 sxs.
2nd. Plug at 1300' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 10-14-2010
INV. NO. 2011060062

RECEIVED
JUL 08 2010
KCC WICHITA

Remarks: BASIC OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Bruce Basye
(TECHNICIAN)

CM