

To: 1 120636  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-23 242  
API NUMBER 15-075-20,491-00-00  
App. NE NE SE, SEC. 28, T. 23 S, R. 43 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 30519  
Operator: Sinclair Oil Corporation  
Name & Address 1625 Broadway, Suite 800  
Denver, CO 80201

2250 feet from S section line  
330 feet from E section line  
Lease Name Hadson-Needsome Farms Well # 9-28  
County Hamilton 165.42  
Well Total Depth 5090 feet  
Conductor Pipe: Size 13" feet 80  
Surface Casing: Size 8 5/8" feet 1128

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Company License Number 30606

Address 250 N. Water, Suite 300, Wichita, KS 67202

Company to plug at: Hour: 2 a.m. Day: 23 Month: 9 Year: 1991

Plugging proposal received from Tom Heskett

(company name) Murfin Drilling Company (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1712'  
1st plug at 3100' with 110 sx cement, 2nd plug at 1720' with 50 sx cement,  
3rd plug at 1150' with 50 sx cement, 4th plug at 750' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:30 a.m. Day: 23 Month: 9 Year: 1991

ACTUAL PLUGGING REPORT 1st plug at 3100' with 100 sx cement,  
2nd plug at 1720' with 50 sx cement,  
3rd plug at 1150' with 50 sx cement,  
4th plug at 750' with 40 sx cement, 5th plug at 40' with 10 sx cement,  
6th plug to circulate rathole with 10 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 03 1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I did not observe this plugging.

Signed Duane Rankin  
(TECHNICIAN) RANK

DATE 10-28-91

INV. NO. 33492  
9-23 NOV 20 1991