

10-29

4-041532

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-23,769-0000

SW NW SW /4 SEC. 10, 11 S, 17 W
1650 feet from S section line
4950 feet from E section line

Operator license# 5293 Lease Tanya well # 2

Operator: Helmrich & Payne, Inc. County Ellis

Address: P.O. Box 558
Garden City, Kansas 67846
Well total depth 3675 feet ^{119.43}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 205 feet
w/160 sx.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 29 Month: October Year: 93

Plugging proposal received from: Lee Fellhaelter

Company: H & P Inc. Phone:

Were: 4 1/2" casing set @ 3674' w/175 sx. cement. Perf. @ 3344' - 3374'. Perfs. salt @ 1800' - Anhy. @ 1050' - Dakota @ 400' - W.L.M. 3350' - T.O.F. @ 1600'. 4 1/2" production casing squeezed @ 690' - 733' with 150 sx. cement (1990). 8 5/8" - 4 1/2" annulus cemented with 350 sx. cement with 6 sx. hulls in cement. Ordered 200 sx. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls. plus 6 sx. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:20P.M. Day: 29, Month: October, Year: 93

Actual plugging report: Perf. 4 1/2" production casing @ 1800' - 1050' - and 400'. Squeezed casing with 25 sx. cement with 200# hulls, followed with 18 bbls. gel mud (6 sx.gel) followed with 175 sx. cement with 300# hulls. Max. 930#. 8 5/8" S.P. - pressured-up to 300# with no sx. cement.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did X aid not] observe the plugging.

Dennis L. Hamel

(agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1993
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED
DATE 11-18-93
39228