

10-29

4-041531

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-051-23,293 - 000

NW NW SW /4 SEC. 10, 11 S, 17 W
2310 feet from S section line
4950 feet from E section line

Operator license# 5293 Lease Tanya well # 1

Operator: Helmrich & Payne, Inc. County Ellis

Address: P.O. Box 558 Garden City, Kansas 67846
Well total depth 3425 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 205 feet w/120 sx.

111.31

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 29 Month: October Year: 93

Plugging proposal received from: Lee Fellhelter

Company: H & P Inc. Phone:

Were: 4 1/2" casing set @ 3398' w/175 sx. cement. Perf. @ 3120' - 3346'. Perfs. salt @ 1800' - Anhy. @ 1050' - Dakota @ 405' - W.L.M. 3300' - T.O.F. @ 1800'. Casing squeezed @ 569' - 599' with 150 sx. cement (1987) and 567' - 598' with 150 sx. cement (1992). 8 5/8" - 4 1/2" annulus squeezed with 300 sx. cement with 6 sx. hulls mixed in cement. Ordered 200 sx. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - plus 6 sx. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:00A.M, Day: 29, Month: October, Year: 93

Actual plugging report: Perf. casing @ 1800' - 1056' - 405'. Squeezed 4 1/2" production casing with 25 sx. cement with 200# hulls, followed with 18 bbls. gel mud (6 sx. gel) followed with 175 sx. cement with 300# hulls. Max. 650#. 8 5/8" S.P. - pressured-up to 300#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] did not [] observe the plugging.

INVOICED
DATE 11-18-93
NO. 39227

HD

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1993
(agent)
Form CP-2/3 CONSERVATION DIVISION
Wichita, Kansas