

15-051-05700-00029

6 040713

API NUMBER 15-(8-1936)

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NENE, SEC. 13, T. 11 S, R. 17 W
4950 - feet from S section line
330 - feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5214
Operator: Lario Oil & Gas
Name & Address: 301 S. Market,
Wichita, KS 67202

Lease Name H. Cross Well # 1
County Ellis 107.41
Well Total Depth 3305 feet
Conductor Pipe: Size 15 1/2 feet 206' w/ 75
Surface Casing: Size 12 1/2 feet 969' w/ 125

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Conty. License Number _____

Address Hays, Kansas

Company to plug at: Hour: 9:00 AM Day: 21 Month: 1 Year: 19 87

Plugging proposal received from Ed. Kasselman

(company name) Lario (phone) _____

were: 7" set @ 3297' w/ 140 sy. O. H - 3305'

Log @ 497-512 w/ 250 sy: C.I.B. @ 3024/3111 - 2965' perf.

Filled w/ drill mud from top perf 2965' to top of mud 2440'

Ordered 450 sy 6 3/8 prog, 10% gel, 2% tile + 12% hulla

Ref 1-21-87 @ 970', 450' & 200' (3 spots per interval)

Plugging Proposal Received by Dennis Z. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 Day: 21 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT Hooked-up to 7" csg & pumped in 160 sy

cmt w/ hulla (cmt. circ out of 15 1/2" cond.) ^{Shut-in &} pumped addit'l

270 sy cmt. w/ hulla down to 7" csg. MAX 600# S.I-300#

Pressured-up 7" 12" annulus w/ 20 sy cmt. - MAX 800#

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-20-87

INV. NO. 16180

Signed Dennis Z. Hamel (TECHNICIAN)