

86

R

3-9

6 061800

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION C W/2 SW SE, SEC. 13, T 11 S, R 17 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-051-02159-0000

660 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5214

Lease Name Pearl Cress Well # 3

Operator Name & Address Lario Oil and Gas Co.

County Ellis 110.31

301 S. Market St.

Well Total Depth 3394 feet

Wichita, Ks. 67202

Conductor Pipe: Size 12 1/2" feet 42 w/50 sks

Surface Casing: Size 8 1/4" feet 1072

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour: 9:00 AM Day: 9 Month: Mar Year: 19 89

Plugging proposal received from Vern Duntz

(company name) Kelso Casing Pulling Inc. (phone) 319-938-2457

were: Order 250 sks 60/40 Poz 8% Gel 3% Cal Cl 5 sk Hulls.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 21 1989  
03-21-89

CONSERVATION DIVISION Plugging Proposal Received by Gilbert G. Scheck  
Wichita, Kansas (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:45AM Day: 9 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT 8 1/4" set at 1072' w/335 sks. 5 3/16" set at

3391' w/125 sks. Top perf at 3391'. Plugged bottom w/sand and 5 sks cement to 3340'.

Shot pipe two times and recovered 1695'. Pumped in 8 1/4" 25 sks cement followed w/5 sks

Hulls in 225 sks cement w/500 psi.

Remarks: B; Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 3-23-89  
INV. NO. 34200

Signed Gilbert G. Scheck  
(TECHNICIAN)  
Gilbert G. Scheck