

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20878-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 32-18S-6W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: CARL FANESTIL Well #: 1
County: RICE Total Vertical Depth: 3178 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3030		
SURF	8.625	214		160 SXS CMT
PROD	4.5	3176		175 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/16/2010 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL
Date/Time Plugging Completed: 06/16/2010 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 3030' AND PUMP 25 SK'S ON TOP OF. PERFORATE AT 950', 600' AND 265'. RUN TUBING TO 950' AND PUMP 35 SX'S OF COMMON CEMENT WITH 3% CALCIUM. PULL TUBING TO 600' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CALCIUM. PULL TUBING TO 265' AND CIRCULATE 60-40 POZ, 4% GEL TO SURFACE. SHUT VALVE ON BACKSIDE OF TUBING AND PUMP CEMENT DOWN BACKSIDE OF 4.5" CASING-UNTIL CIRCULATED UP OUT OF 4.5". PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3081	3085	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 06 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 10-14-2010
INV. NO. 2011060034

Remarks: 60-40 POZ, 4% GEL UNLESS OTHERWISE SPECIFIED. LOG TECH OF KS #6108. COPELAND TICKET C-37074. GPS READING IS 317' FSL & 2319' FEL-DONE ON 6-16-10.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)