

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22836-00-00  
Spot: SWNENW Sec/Twnshp/Rge: 2-13S-16W  
990 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: BOXBERGER Well #: 5  
County: ELLIS Total Vertical Depth: 3525 feet

Operator License No.: 5145  
Op Name: DREILING OIL INC  
Address: 1008 CODY AVE PO BOX 550  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	167	0	130 SX
T1	2.375	3500		
PROD	5.5	3523	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2010 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY W. PIESKER Company: DREILING OIL, INC. Phone: (785) 735-4363

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 07/02/2010 10:15 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tubing parted around 700'.  
Tried for three days to get hold of tubing and/or get down the well.  
Could not make any progress. Nothing on impression block - bit bouncing.  
Ran tubing to 720'. Circulated with 85 sxs 60/40 pozmix - 4% gel.  
POOH. Tied onto casing and pressured to 500# P.S.I. with 15 sxs cement.  
Pressured backside to 200# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3381	3390		
3362	3364		
3343	3354		
3284	3286		
3280	3282		
3246	3249		
3229	3232		
3203	3207		
3170	3174		

RECEIVED  
JUL 08 2010  
KCC WICHITA

INVOICED  
DATE 10-14-2010  
INV. NO. 2011060037

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_



(TECHNICIAN)

JUL 06 2010

