

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-21072-00-00
Spot: NESWSESW Sec/Twnshp/Rge: 5-22S-4E
370 feet from S Section Line, 3472 feet from E Section Line
Lease Name: LATHROP-HAWK Well #: 2-A
County: MARION Total Vertical Depth: 2549 feet

Operator License No.: 6131
Op Name: DRILLERS & PRODUCERS, INC.
Address: PO BOX 385
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		150sx
PLG3	4.5	2546	353	200 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2010 11:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: PHILLIPS WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 06/30/2010 4:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:
6/30/2010 PHILLIPS WELL SERVICE RAN TUBING TO 2350'. CONSOLIDATED TIED ON AND PUMPED A 70 SX BOTTOM PLUG. PHILLIPS PULLED TUBING AND SHOT OF CASING AT 353'. PHILLIPS PULLED CASING AND RAN IN TUBING TO 270'. CONSOLIDATED TIED ON AND CIRCULATED CEMENT TO SURFACE. PHILLIPS PULLED TUBING, AND CONSOLIDATED TOPPED OFF HOLE. PLUGGING FINISHED AT 4:15PM. TK #28484: 70 SXS CLASS A W/3% CAC1 & 119 SX CLASS A FOR A TOTAL OF 189 SX. 7/5/2010 BILL HANSON CALLED SAYING TOP PLUG WAS DOWN 20' AND THAT THEY WERE DRY SACKING IT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2350	2357	CSG	

INVOICED
DATE 10-14-2010
INV. NO. 2011060038

RECEIVED
JUL 19 2010
KCC WICHITA

Remarks: PLUGGED DUE TO DENIED TA
Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

✓