

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00736-00-01
Spot: SWSENE Sec/Twnshp/Rge: 28-1S-18W
2954 feet from S Section Line, 1083 feet from E Section Line
Lease Name: JACKSON E Well #: 2
County: PHILLIPS Total Vertical Depth: 3517 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S YALE # 702
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	214	0	150 SX
PROD	5.5	3515	0	150 SX

Well Type: EOR UIC Docket No: E06746.5 Date/Time to Plug: 07/23/2010 10:00 AM
Plug Co. License No.: 31569 Plug Co. Name: BACH, JASON DBA BACH OIL PRODUCTION
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered 280 sxs 60/40 pozmix - 4% gel - 500# hulls - 10 sxs gel spacer.
Perforated at 1790' - 1210' - 260'.
Junk in the hole at 3322'.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2010 2:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing down to 3322' to tag. Pulled one joint - pumped 10 sxs gel spacer - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1790' - pumped 180 sxs 60/40 pozmix - 4% gel with 200# hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing with 5 sxs 60/40 pozmix - 4% gel.
Hooked to 8 5/8" x 5 1/2" annulus. Pumped 25 sxs 60/40 pozmix - 4% gel.
S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
3442	3446		
3425	3431		

INVOICED
DATE 10-14-2010
INV NO. 2011060039

Remarks: ALLIED CEMENTING COMPANY-TICKET #39043.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

(M)

RECEIVED

Form CP-2/3

JUL 29 2010

KCC WICHITA

JUL 26 2010

NATIONAL ASSOC PETROLEUM #2 JACKSON "E" 28-1-18W SW SE NE

Contr. FERRELL DRILLING COMPANY PHILLIPS County

E 2187RB Comm. Comp. 2-1-52 IP 183 BOPD (LANS) PHY POT

Tops	Depth	Datum	Casing
			8" 214 PERF 16 S, 3442-46
			5" 3515 25 S, 3425-31
			ACID 3000
LANS	3369	-1182	
T.D.	3517	-1330	

HUFFSTUTTER POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS